



45' CONCRETE PAVEMENT SECTION
TYPICAL CROSS SECTION

NTS

- NOTES:
1. TRANSVERSE SAWED CONTRACTION JOINTS AT 15' INTERVALS & LONGITUDINAL SAWED CONTRACTION JOINTS AT 11' INTERVALS FOR CONCRETE PAVEMENT.
 - * 2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 36#/SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
 - ** 3. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 30#/SY.

DATE	BY	CHECKED	DATE
APPROVED 2/11	DESIGNED 2/11	APPROVED 2/11	DESIGNED 2/11
 CITY OF ARLINGTON, TEXAS PROJECT NUMBER PROJECT NAME (PROJECT LIMITS)			