

SECTION NO. 15

SPECIAL PROVISIONS - PAVEMENT MARKING SPECIFICATIONS

Pavement markings shall include Reflectorized Pavement Markings, Prefabricated Pavement Markings, and Raised Pavement Markers and shall be in accordance with the Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges as published by the Texas Department of Transportation, latest edition. Contractor shall place markings in accordance with the surface condition, moisture, and temperature requirements.

Reflectorized Pavement Markings that are considered the final and permanent markings shall be Type I "Hot Applied Thermoplastic, unless otherwise noted on the plans or approved by the engineer. Prefabricated pavement markings shall be placed in accordance with the manufacturer's specifications.

Payment for pavement markings shall be in accordance with the various bid items as shown in the PROPOSAL.

Contractor shall also furnish, place, maintain, and remove temporary Work Zone Pavement Markings. Work Zone Pavement Markings are considered part of the Traffic Control Plan and are considered subsidiary to the other bid items.

END OF SECTION