



Department of Public Works and Transportation

Blue Forest Drive street improvements – scheduled to begin the week of July 20, 2015!



Expect traffic delays

Blue Forest Drive improvements are included as part of the City of Arlington Tri- Schools Street Improvements construction project. Please see: www.Arlingtontx.gov/trischools

Scheduled to begin Monday, July 20, **the section of Blue Forest Drive between Ledbetter Road to almost Forest Mist Drive** will have the first of a series of construction operations begin. During the week of July 20, the existing asphalt pavement and subgrade will be pulverized and about the top 6 inches hauled off. The next construction phase is scheduled to begin Monday, July 27 and last about two days. Lime and then concrete will be mixed into the pulverized street base. Friday, July 31 about 4 inches of asphalt base will be installed. August 3 and/or August 4, the final 2-inches of asphalt will be installed on Blue Forest Drive between Ledbetter Road and West Harris Road.

In the section of Blue Forest Drive between West Harris Road to just past Forest Mist Drive, sometime during the week of July 27 the City contractor will remove (mill off) the top two inches of the asphalt street surface. This operation should only take one day. A day or so before or after the milling operation, localized street failures will be repaired. On or about Monday August 3 and/or August 4, a new asphalt surface will be installed on Blue Forest Drive between West Harris Road and Ledbetter Road.

Traffic access will be limited during these various construction operations, please follow flagmen instructions. It is likely you may need to drive around the block and/or temporarily park on a side street. Access to and from your driveway will generally be open for overnight parking. Access will be impacted or temporarily restricted between 7am to about 6 pm will construction is underway.

Rain, equipment failure and unexpected... will impact the construction schedule. We request and need your patience and help! **Expect about 10 to 15 minute delays and changing access routes.**

Please do not park your car on the street during the weeks of construction.

Please feel free to contact me if there are any questions or concerns. If I'm unavailable, please contact Marvin Cottongame @ 817 459 6550. My thanks and appreciation for your patience and understanding as we build these needed improvements.

Steve Schell, P.E. - Project Manager - City of Arlington - 817 459 6152