



NOTE:
 FOR LINES BEING LAID PRIOR TO NEW STREET CONSTRUCTION WHICH WILL LIE BENEATH PAVEMENT OR CURB AND GUTTER, BACKFILL ABOVE PIPE EMBEDMENT SHALL CONSIST OF NATIVE MATERIAL, COMPACTED IN MAX. 6" LIFTS TO 95% STANDARD PROCTOR DENSITY AT OPTIMUM MOISTURE CONTENT $\pm 2\%$.

FIGURE 26
STREET BACKFILL PRIOR TO STREET CONSTRUCTION
ARLINGTON WATER UTILITIES